



Article

# DMSO and TMAO—Differences in Interactions in Aqueous Solutions of the K-Peptide

Julia Godlewska <sup>1</sup>, Bartosz Cieśla <sup>2</sup>, Jarosław Wawer <sup>1</sup> and Piotr Bruździak <sup>1,\*</sup>

<sup>1</sup> Department of Physical Chemistry, Gdańsk University of Technology, Narutowicza 11/12, 80-233 Gdańsk, Poland; s180776@student.pg.edu.pl (J.G.); jaroslaw.wawer@pg.edu.pl (J.W.)

<sup>2</sup> Department of Inorganic Chemistry, Gdańsk University of Technology, Narutowicza 11/12, 80-233 Gdańsk, Poland; s180816@student.pg.edu.pl

\* Correspondence: piotr.bruzdziak@pg.edu.pl

**Abstract:** Interactions between a solvent and their co-solute molecules in solutions of peptides are crucial for their stability and structure. The K-peptide is a synthetic fragment of a larger hen egg white lysozyme protein that is believed to be able to aggregate into amyloid structures. In this study, a complex experimental and theoretical approach is applied to study systems comprising the peptide, water, and two co-solutes: trimethylamide *N*-oxide (TMAO) or dimethyl sulfoxide (DMSO). Information about their interactions in solutions and on the stability of the K-peptide was obtained by FTIR spectroscopy and differential scanning microcalorimetry. The IR spectra of various osmolyte–water–model-peptide complexes were simulated with the DFT method (B3LYP/6-311++G(d,p)). The FTIR results indicate that both solutes are neutral for the K-peptide in solution. Both co-solutes affect the peptide to different degrees, as seen in the shape of its amide I band, and have different influences on its thermal stability. DFT calculations helped simplify the experimental data for easier interpretation.

**Keywords:** biomolecular interactions; amyloid; intermolecular interactions; protein–ligand binding; chaperones; microcalorimetry; spectroscopic techniques; DFT calculations



**Citation:** Godlewska, J.; Cieśla, B.; Wawer, J.; Bruździak, P. DMSO and TMAO—Differences in Interactions in Aqueous Solutions of the K-Peptide. *Int. J. Mol. Sci.* **2022**, *23*, 1872. <https://doi.org/10.3390/ijms23031872>

Academic Editor: Irina M. Kuznetsova

Received: 18 January 2022

Accepted: 4 February 2022

Published: 7 February 2022

**Publisher's Note:** MDPI stays neutral with regard to jurisdictional claims in published maps and institutional affiliations.



**Copyright:** © 2022 by the authors. Licensee MDPI, Basel, Switzerland. This article is an open access article distributed under the terms and conditions of the Creative Commons Attribution (CC BY) license (<https://creativecommons.org/licenses/by/4.0/>).

## 1. Introduction

Protein or peptide aggregation is a natural phenomenon that, in certain circumstances, can be dangerous. One such deleterious process is the formation of amyloid fibrils. Amyloids are large protein aggregates that are resistant to many degradation mechanisms that arise as a result of improper folding. The structure of amyloids is rich in  $\beta$ -sheets [1], and the formed aggregates are unbranched and long and have diameters in the range of nanometers (2–12 nm) [2,3]. Around 40 diseases are believed to be linked to the formation of amyloids [4], including Alzheimer's disease, Parkinson's disease, and type II diabetes.

The role of such protein assemblies in pathogenesis is unknown or even questioned. Oligomers have been suggested to potentially be more toxic than mature fibrils [5,6]. The biochemical systems involved in fibrillation are complex, and several possible routes have been identified in the regulation of this process [7]. However, the amyloidogenic potency of the protein itself is one of the key factors that undoubtedly plays an important role in this process. Some amino-acid sequences have been shown to have a greater ability to form amyloids [8]. The role of aromatic AA residues is especially important [9]. Keeping all of this in mind, great effort has been undertaken to identify the core part of a protein that triggers amyloidogenesis [10–12].

Due to the slow kinetics of amyloidogenesis and other difficulties related to in vitro studies, the exact mechanism of in vivo aggregation is still under debate. Moreover, such a vague connection between aggregation and pathogenicity makes developing a treatment method more difficult. Thus, studies on amyloid formation are an emerging direction of

modern biochemistry. Research on the properties of model systems is particularly helpful in this matter.

Hen egg white lysozyme (HEWL) is one of the most extensively investigated model proteins for which fibrillation analyses have been undertaken. A coarse estimation of the core amyloidogenic sequence of HEWL was performed in the early 2000s [13,14]. Almost a decade later, the position of this region was further determined with higher precision by Sugimoto et al. [15,16]. This fragment consists of residues 54–62 GILQINSRW and was named the K-peptide. The effect of fibrillation conditions on HEWL amyloidogenesis was tested on many occasions. Among others, the influences of temperature and pH [17], fibrillation in the presence of low molecular additives [18–20], impact of ionic strength [21], and shear or stirring rate [22,23] were examined. Investigations on peptide fibrillation have been much more limited. However, certain issues still remain unexplored. For example, dimethyl sulfoxide (DMSO) is frequently used to improve the solubility of the substrate [16] or investigated additives [24,25], but examinations on how this solvent influences amyloidogenesis have been rarely conducted [23].

In this work, we attempt to answer whether DMSO can interact with the K-peptide in a solution. Then, our findings are compared with those for another similar system comprising trimethylamine *N*-oxide (TMAO), for which the stabilizing properties are well known and described [26–29]. Both compounds are important chemical chaperons widely used to improve the thermal- and cryo-stabilization, aggregation, folding, etc. of macromolecules. Although similar in size and overall structure, they act differently and affect solvent media in different manners [30,31]. Some protocols focus on the measurement and isolation of these osmolytes' spectra. Such spectra are easier to analyze and less convoluted than the FTIR spectra of peptides but provide the same information about possible osmolyte–peptide interactions. The role of molecular interactions, elucidated with the aid of our studies, may provide deeper insights into the mechanism of amyloid formation.

## 2. Materials and Methods

All solutions of TMAO ( $\geq 99.0\%$ , Sigma-Aldrich, Darmstadt, Germany), DMSO ( $99.9 + \%$ , Alfa Aesar, ThermoFisher GmbH, Kandel, Germany), and the K-peptide ( $98\%$ , Lipopharm.pl, Zblewo, Poland) were prepared by weight using a XS205 DualRange analytical balance (Mettler Toledo, Greifensee, Switzerland). The densities of DMSO and TMAO solutions at  $25.000\text{ }^\circ\text{C}$  were measured using a DMA 5000 densimeter (Anton Paar, Graz, Austria). The densities of the K-peptide solutions were approximated using the partial molar volume of a peptide equal to  $0.73\text{ cm}^3\cdot\text{g}^{-1}$ . The densities were necessary to calculate the proper molar concentrations ( $\text{mol}\cdot\text{dm}^{-3}$ ).

### 2.1. ATR-FTIR Spectroscopy

All ATR-FTIR spectra were collected using a Nicolet 8700 FTIR spectrometer (Thermo Scientific, Waltham, MA, USA) and OMNIC software (Thermo Scientific, Waltham, MA, USA). The spectrometer was equipped with a six-reflection Ge crystal thermostated ATR accessory (Specac Ltd., Orpington, Great Britain), KBr beamsplitter, DTGS-TEC detector, and EverGlo IR source (all from Thermo Scientific, Waltham, MA, USA). A thermal circulator (Julabo GmbH, Seelbach, Germany) was used to maintain the temperature of the ATR accessory at a constant level of  $25.0 \pm 0.1\text{ }^\circ\text{C}$ . Each spectrum was an average of 256 independent scans with a resolution of  $2\text{ cm}^{-1}$ . The spectrometer and the accessory were purged with dry nitrogen (NiGen LCMS 40-1 nitrogen generator, Claind, Lenno, Italy). However, any excess water vapor contribution was subtracted with the aid of our recently developed algorithm [32].

For each osmolyte (DMSO and TMAO), two kinds of solution series were prepared. The first one consisted of six solutions of a fixed molar concentration of osmolyte (DMSO:  $6.7 \pm 1.2\text{ mol}\cdot\text{dm}^{-3}$ ; TMAO:  $2.02 \pm 0.08\text{ mol}\cdot\text{dm}^{-3}$ ) and varying K-peptide concentration within the range  $0.0\text{--}40.0\text{ mg}\cdot\text{mL}^{-3}$ . The easiest way to prepare this series is, first, to prepare six K-peptide aqueous solutions of various concentrations; next, dissolve a fixed amount of

the osmolyte in a fixed volume of the K-peptide's solution to maintain a constant molar concentration of the osmolyte. Errors during the preparation procedure are inevitable, but precise analytical balance and weighing each solution at each preparation step allowed us to minimize these errors and to calculate the molar concentrations or molalities necessary for the next steps with high confidence. This series was used to determine if any interaction between the osmolyte and K-peptide were formed. The second kind of solution series consisted of five aqueous solutions of the osmolyte, where its concentration was close to that of the first series but varied slightly in each sample (DMSO:  $6.07 \div 4.50 \text{ mol}\cdot\text{dm}^{-3}$ ; TMAO:  $2.93 \div 1.31 \text{ mol}\cdot\text{dm}^{-3}$ ). This series allowed us to determine the influence of concentration changes on the band shape of DMSO or TMAO spectra. Spectra of all solutions were collected 1 to 2 h after their preparation. In the case of the DMSO solutions, the K-peptide was fully soluble, while in the presence of TMAO, the K-peptide formed a suspension rather than a typical peptide/protein solution. However, the goal of these studies was to investigate the intermolecular interactions with a focus on the vibrational structure of the DMSO or TMAO molecule in such systems. All of the spectra for water were accounted for during analysis (as they have an easily recognizable difference in bands in the OH bending region  $1700\text{--}1600 \text{ cm}^{-1}$ ) according to its molar concentration in a sample. Next, all of the spectra were divided by the factor of  $1/C_{\text{DMSO or TMAO}}$ , which allowed us to obtain the molar spectra of DMSO or TMAO in their pure solutions or solutions of the K-peptide. Such a normalization procedure is necessary to visualize the changes in spectra with the aid of a derivative spectrum and with greater confidence.


A variant of the difference spectra method was applied to extract the so-called derivative or changeability spectra from each series (sometimes called excess spectra). This name should not be confused with ordinary spectra derivatives. The derivative is defined as  $(\partial\epsilon/\partial m)_{m=0}$ , where  $\epsilon$  is the molar absorption coefficient at a given wavenumber of a molar spectrum and  $m$  is the molality of the solution ( $\text{mol}\cdot\text{kg}_{\text{water}}^{-1}$ ), and details of the calculation method can be found in our previous papers [33,34]. This derivative emphasizes small, sometimes obscure, variations in spectral series, i.e., shifts, or width or intensity changes in IR bands. Then, these alterations can be interpreted with the aid of DFT calculations in the context of intermolecular interactions. This kind of spectrum also serves to calculate "affected spectra"; however, in this paper, all of the information available directly from the derivative spectrum was sufficient.

## 2.2. Differential Scanning Calorimetry

All calorimetric measurements were performed using a nanoDSC III calorimeter (Calorimetry Sciences Corp., Lindon, UT, USA) equipped with platinum capillary cells (300  $\mu\text{L}$ ). Deionized water was used as a reference. A water–water scan with four re-scans and a K-peptide–water scan with one re-scan in the range of  $10\text{--}100 \text{ }^\circ\text{C}$  and a scanning speed of  $1 \text{ }^\circ\text{C}\cdot\text{min}^{-1}$  were collected. The K-peptide concentration was set to  $2 \text{ mg}\cdot\text{mL}^{-1}$  for a satisfactory signal intensity with relatively low signal-to-noise ratio.

## 2.3. DFT Calculations

All quantum mechanical calculations were performed with the help of supercomputers of the Academic Computer Center (TASK, Gdańsk, Poland) with Gaussian 09.revD01 software [35]. Final structures were optimized at the B3LYP/6-311++G(d,p) level of theory [36–38], including the CPCM solvent model [39,40] and the GD-BJ3 dispersion correction [41] at the final calculation steps. The selected DFT method is optimal for small organic molecules, while the selected basis set provides a satisfying accuracy of calculation and a good agreement with real-life systems. All of the preparatory structures (see Scheme 1) were prepared, and the visualization of results were performed with the Avogadro v.1.2.0 software (Kitware, Inc., NY, USA) [42].



**Scheme 1.** Chemical structures of molecules used for DFT calculations.

The calculations were performed according to the following procedure, which is similar to that presented in our previous paper [43]: (1) the raw structures of all system components (TMAO, DMSO, and NAGMA) were first optimized in vacuo, and then, the results of this preparatory step were optimized within the CPCM solvent model; (2) the water molecules were added to these optimized structures close to various interaction sites, and then, each system was optimized again; and (3) the optimized complexes exhibiting the lowest energies were combined in all possible variations and configurations to form larger systems of NAGMA, water, and TMAO or DMSO and were optimized again. None of the resulting complex structures exhibited negative vibration frequencies.

Based on the results of the theoretical calculations, the cause of specific shifts and intensity changes in the experimental IR of the complexes were identified. In this paper, we focused mainly on the possibility of the formation of direct or indirect interactions between NAGMA and TMAO or DMSO.

### 3. Results and Discussion


#### 3.1. Does the K-Peptide Have ANY Structure in a Solution?

Before any interaction studies could be performed, an additional experimental step had to be performed for the K-peptide. Theoretically, without any a priori knowledge, we can assume that in aqueous solutions, this short peptide has a few different structures. These structures can be divided into two main groups: unstructured (or unfolded) free peptide, and structured (or organized) peptide or its clusters. The interpretation of other experimental and computational results depends on the characteristics of the structure; thus, using two experimental methods, we had to determine the structural type first.


ATR-FTIR spectroscopy of the aqueous protein sample gives information about the secondary structures present in a peptide solution. First, the K-peptide was re-suspended in deionized water to a final concentration of  $40 \text{ mg}\cdot\text{mL}^{-1}$ , and its ATR-FTIR spectrum was measured. The amide I band of the K-peptide was uncovered by subtracting the pure water spectrum (see Figure 1). The shape of the band indicates that  $\beta$ -sheets are its main component: the most predominant sub-band in the whole region is the  $\beta$ -sheet indicator band at ca.  $1625 \text{ cm}^{-1}$ . Usually, the band shape of the amide I region of unstructured peptides exhibits a broad sub-band with a maximum at ca.  $1650 \text{ cm}^{-1}$ . This sub-band is not present in the K-peptide spectrum; thus, we provide evidence that the peptide is folded in water. However, as the K-peptide is assumed to form  $\beta$ -amyloid structures, the folded form can be polydispersed. The other experiments and calculations were not affected by these results, but knowing what kind of structure is present in the solutions is necessary.

Differential scanning calorimetry (DSC) provides this knowledge of the types of structures present in the solutions. The K-peptide suspension ( $1.0 \text{ mL}$  of  $2 \text{ mg}\cdot\text{mL}^{-1}$ ) was placed in one cell of the calorimeter, while pure water was placed in the reference cell. The resulting thermogram is presented in Figure 2 (red line). We decided not to convert the raw thermograms to the molar  $C_p(T)$  because the exact concentration and molar mass of the peptide aggregate were uncertain. The presented graphs were calculated as the differences between the thermograms corresponding to the peptide's solution and the pure water, DMSO, or TMAO solution; hence, the  $\Delta$  sign in the  $\mu\text{J}/\text{s}$  axis. Only a straight line was used for the baseline correction because the characteristics of each transition did not allow us to use the more common sigmoidal (or "chemical") function. However, such raw thermograms provided sufficient information about K-peptide denaturation, and a conclusion

could be drawn. The thermogram exhibited a characteristic broad denaturation transition to polydispersed polymers. The abrupt ending of the band at ca. 85 °C for the K-peptide in pure water indicates that the slow denaturation process is terminated by an irreversible denaturation step (a re-scan confirmed this observation; data not shown). The exact denaturation would have higher transition temperature than the maximum 100 °C of the measurement, as indicated by the rising slope of the thermogram. In the case of a more standard single peptide or protein molecules with well-defined structures, the recorded bands are much narrower, while amorphous aggregates exhibit a complex set of transitions [44]. The K-peptide cannot be clearly classified into any of the above-mentioned categories, and the hypothesis that the K-peptide forms polydispersed  $\beta$ -amyloid structures is correct.



**Figure 1.** The amide I and II regions of the ATR-FTIR spectrum of the K-peptide in solution. The predominant  $\beta$ -sheet band (ca. 1625 cm<sup>-1</sup>) is marked.



**Figure 2.** Raw thermograms of the K-peptide in different solutions. The maximum of each graph is marked with an appropriate temperature.

### 3.2. FTIR

The spectra isolation method used in this work allows us to extract information on possible small changes in the shape of a given solution component. With a fixed osmolyte concentration, only changes caused by the presence of the K-peptide can be detected. However, the amount of water in a sample also changes because the volume of the peptide imposes a lower number of water molecules in the solution if the osmolyte's concentration

is fixed. Thus, small changes due to hydration/dehydration of the osmolyte may occur in such situations and must be taken into account. Without this procedure, all changes in the solution spectra could be falsely ascribed to osmolyte–K-peptide interactions. The easiest way to verify if the observed band shape is caused by such a phenomenon is to measure a series of osmolyte's solutions' spectra in the same range, where each spectrum corresponds to a slightly different osmolyte's concentration. A changeability (or excess) spectrum can be easily calculated from such a series and compared with the one corresponding to the osmolyte–K-peptide system.


DMSO and TMAO virtually do not directly interact with the K-peptide in aqueous solutions. Although changeability spectra are not flat and some difference bands are present, all of these changes in band shape can be easily attributed to the change in the osmolyte–water concentration ratio. All major shifts in the osmolyte bands (marked with red boxes) are exactly the same in the case of both the osmolyte–water–K-peptide and osmolyte–water systems (Figure 3). Some additional bands, marked with asterisks, can be easily ascribed to the K-peptide self-bands or changes in the water OH-bending band. Although the molar concentration of osmolyte in the system with the K-peptide is constant, the presence of the peptide causes dehydration of the osmolyte. In other words, a simple competition between DMSO or TMAO and the K-peptide occurs for the water molecules. The osmolyte is hydrated to a smaller extent when the peptide is present in the solution, and the same is true for the peptide.

Concluding whether such a phenomenon is favorable or unfavorable from the peptide stability point of view is difficult. However, a comparison of the K-peptide amide I bands in various solutions (see Figure 4) clearly indicates that C=O bonds are weaker when compared with the pure water solution in the case of TMAO (shifts to lower wavenumbers, ca.  $1621\text{ cm}^{-1}$ ) and stronger in DMSO solutions (shift to higher wavenumbers, ca.  $1627\text{ cm}^{-1}$ ). Stronger C=O bonds translate to weaker hydrogen bonds in the  $\beta$ -sheet structure. Thus, the  $\beta$ -sheet structure, based mainly on intramolecular hydrogen bonds, appears to be stronger in the solution of TMAO. Moreover, the shape of the amide band in a water solution can be considered a superposition of these two populations of C=O bond types, as the the wider  $\beta$ -sheet band is clearly composed of two sub-bands, corresponding roughly to well-defined single  $\beta$ -sheet peaks in DMSO and TMAO solutions. As no direct interactions are formed in solutions of both osmolytes, these changes in the shape of the amide I band of the K-peptide can be ascribed to modifications of its nearest solvent neighborhood.


### 3.3. DFT

The DFT calculations gave insights into the possible interactions between various mixture components. The selected optimized structures of the complexes from Table 1 are presented in Figure 5. Although the systems were minimal (NAGMA instead of a long polypeptide chain, the CPCM model, and an additional water molecule), the IR results are in good agreement with general observations drawn from the theoretical calculations. In our previous papers, such systems reflected the changes in the band shape of the OD band well in similar complex solutions [33,45].

An isolated DMSO molecule exhibited a high-intensity S=O stretching band at  $942\text{ cm}^{-1}$ , and any interaction weakened this bond and shifted its position to higher wavenumbers ( $941.93 \pm 4.1\text{ cm}^{-1}$ , based on 12 structures). If the shift originated in the DMSO–water or DMSO–NAGMA, interaction was irrelevant. However, in one significant outlier structure, NAGMA–DMSO–H<sub>2</sub>O–2,  $922.86\text{ cm}^{-1}$ , the S=O bond was almost perpendicular to the N–H bond of NAGMA, i.e., the DMSO surface was closer to the surface of NAGMA in contrast with other optimized structures, where the angle between these two bonds was always larger than  $90^\circ$ . Such a large shift, indicating a direct DMSO–NAGMA interaction, should be visible in the FTIR spectrum; however, all changes within the range of the S=O band are virtually identical for the DMSO–water and DMSO–water–NAGMA systems. Thus, we can conclude that direct interactions between DMSO and NAGMA are so rare that detecting them with a conventional FTIR setup is impossible.



**Figure 3.** Isolated changeability spectra of DMSO (a) and TMAO (b) systems corresponding to possible interactions in aqueous solutions. Blue dashed lines correspond to pure component spectra. The most important differential bands and corresponding bands in ordinary spectra are marked with rectangles. Concentrations of TMAO or DMSO in the case of red graphs varied to reflect changes in the molar absorption caused solely by changes in the amount of water available. The concentrations of these compounds, presented as black graphs, was fixed to obtain only the parts of the spectra that correspond to changes caused by the presence of the K-peptide. Band regions ascribed to the K-peptide and water are marked with asterisks. The intensities of all graphs were adjusted for easy comparison of the changes and to fit the panel.




**Figure 4.** The amide I region of the K-peptide ATR-FTIR spectra in pure water and in the presence of TMAO or DMSO. All spectra correspond to the highest available concentrations of the K-peptide, and TMAO or DMSO.

**Table 1.** The position of stretching vibrations of S=O and N–O bonds of DMSO and TMAO, respectively, obtained for optimized structures of aqueous complexes with the NAGMA peptide model. The structures were selected according to the lowest energy criterion (energies calculated with the B3LYP/6-311++G(d,p) level of theory).

Structure	$\nu_{S=O}^1/\text{cm}^{-1}$	$\nu_{S=O}^2/\text{cm}^{-1}$
DMSO	941.93	1009.35
DMSO-H <sub>2</sub> O	931.11	1011.53
NAGMA-DMSO-1	932.07	1015.58
NAGMA-DMSO-2	934.79	1009.37
NAGMA-DMSO-H <sub>2</sub> O-1	931.74	1010.46
NAGMA-DMSO-H <sub>2</sub> O-2	922.86	1010.81
NAGMA-H <sub>2</sub> O-DMSO-1	929.71	1008.20
NAGMA-H <sub>2</sub> O-DMSO-4	930.80	1009.07
NAGMA-H <sub>2</sub> O-DMSO-6	927.57	1015.93
NAGMA-H <sub>2</sub> O-DMSO-7	936.52	1007.59
NAGMA-H <sub>2</sub> O-DMSO-10	932.60	1012.42
Structure	$\nu_{N-O}^1/\text{cm}^{-1}$	$\nu_{N-O}^2/\text{cm}^{-1}$
TMAO	935.37	—
TMAO-H <sub>2</sub> O	946.20	—
TMAO-2xH <sub>2</sub> O	951.66	—
TMAO-3xH <sub>2</sub> O	955.62	—
NAGMA-TMAO-1	942.06	—
NAGMA-TMAO-2	943.53	—
NAGMA-TMAO-H <sub>2</sub> O-1	952.66	—
NAGMA-TMAO-H <sub>2</sub> O-2	950.02	—
NAGMA-H <sub>2</sub> O-TMAO-1	940.77	947.86
NAGMA-H <sub>2</sub> O-TMAO-2	949.48	950.68
NAGMA-H <sub>2</sub> O-TMAO-3	941.65	947.13
NAGMA-H <sub>2</sub> O-TMAO-4	942.02	948.17
NAGMA-H <sub>2</sub> O-TMAO-5	953.49	—





**Figure 5.** Optimized structures of DMSO, TMAO, NAGMA, and their complexes. The names of these structures are the same as in Table 1.

TMAO-based systems act differently. The addition of water to an isolated TMAO molecule causes a shift in the N–O stretching band, ca.  $935\text{ cm}^{-1}$ , toward higher wavenumbers, which indicates that the N–O bonds become stronger when TMAO and water interact (a shift to ca.  $940\text{--}945\text{ cm}^{-1}$ ). The almost single N–O bond in this case takes on the nature of a double bond. The analogous bond in the DMSO molecule is stronger in the isolated molecule, and an interaction does not exert such a strong impact on its quality, as seen in the FTIR spectra and DFT calculation results.

Although the behavior of the N–O bond in different environments seems illogical, this behavior is well reflected in the shifts predicted by the DFT calculations. If the tri- or di-hydrated TMAO is taken as a reference structure, a TMAO–NAGMA interaction causes the N–O band to shift to lower wavenumbers. The results of the DFT calculations do not

exclude the possibility of close TMAO–water–peptide interactions. However, such a direct interaction should be accompanied with the formation of an additional band originating in a different frequency than the N–O bond, which interacts with water molecules of the K-peptide hydration shell (a split of the N–O band). This formation is not observed in the experimental spectra; thus, we conclude that such interactions are non-existent. Such a conclusion stays in good agreement with our previous experimental investigation of doubly affected water in systems of TMAO and model dipeptides [31]. In light of the MD simulation from that paper, the better hydration of the N–O group (i.e., an effect similar to dissolution) can be caused by preferential hydrophobic TMAO–peptide interactions: the N–O group is preferentially oriented toward bulk water. Although this interaction cannot be verified with our scheme of DFT calculations, the preferential hydration of TMAO and the accompanying dehydration of the peptide are well reflected in the DSC results.

### 3.4. DSC Results

As mentioned earlier, the K-peptide suspended in water is fairly stable, and the slow denaturation transition is terminated at very high temperatures (presumably higher than 90 °C) by irreversible denaturation. Any addition to the solution (DMSO or TMAO) significantly lowers the denaturation temperature and changes the overall characteristics of the transition.

TMAO is generally considered a good protein stabilizer. However, as seen in our previous paper, TMAO promotes the strong thermal irreversible aggregation of some proteins. The K-peptide is no different, and the thermogram obtained for the TMAO–peptide system reflects this fact very well. The initial slow denaturation process of the peptide complex structure is completely changed when TMAO is present in a solution. First, TMAO makes solvating the peptide difficult, as most K-peptides do not re-suspend well in the presence of an osmolyte. The supernatant, which was collected for the DSC experiment, had a significantly lower peptide concentration, yet the enthalpy of denaturation was significantly higher than that for the fully re-suspended peptide in pure water. The maximum of the denaturation peak was also lowered and accompanied by a strong irreversible transition (no peak was observed in the re-scans). The exact structure of the K-peptide in a solution is not known; however, poor hydration in the presence of TMAO, as we concluded on the basis of FTIR and DFT results, significantly destabilizes it thermally in contrast with the pure K-peptide solution. Moreover, the pre-transition peak (about 50 °C) may indicate that, at this temperature, some suspended peptide aggregates are broken down into smaller fragments, which are then highly destabilized by an unfavorable solvent properties, modified by the presence of the osmolyte. Hence, the denaturation involves high peptide–water structure reorganization and a significantly higher enthalpy of denaturation is observed, despite the fact that the concentration of the K-peptide is smaller than in the case of pure water and DMSO solutions.

DMSO, on the other hand, exhibits slightly more destabilizing properties than TMAO in terms of denaturation temperature. Although the solubility of the K-peptide is much higher than in the case of other two kinds of solution, the enthalpy of transition is the lowest, and the asymmetry of the peak indicates an irreversibility of the process (confirmed with the lack of any peaks in the re-scan).

## 4. Conclusions

In light of our experimental and theoretical results, we conclude that both DMSO and TMAO do not interact directly with the K-peptide in an aqueous solution. Although some changes in the vibrational structure of both osmolytes are visible in the FTIR spectra, when the peptide is present in their solutions, they can be ascribed solely to the effect of a concentration change. All FTIR spectra changes can be explained in term of simple solution mixing when co-solutes (i.e., the osmolytes and the peptide) do not interact with each other, and at least at the level of intermolecular interactions, both osmolytes stay neutral for the K-peptide.



Both osmolytes, DMSO and TMAO, favor diluted solutions and prefer interactions with water molecules. However, in both cases, the mechanism of this preference is different. DMSO hydration is hydrophobic in nature [30], yet this molecule regains some rotational freedom in a fully closed hydration cage, and its hydration is favorable from an entropic point of view. In more concentrated solutions, a not fully developed hydration layer is held down by favorable weak interactions. Thus, the decrease in available water in its surrounding, caused by the addition of the K-peptide, forces the DMSO molecule to hold to all available water without any formation of new interactions with the peptide or its aggregates surface. The hydration of TMAO is different from that of DMSO, and the most important forces driving those interactions are enthalpic in nature [31]. Very strong interactions with water and a relatively high number per TMAO molecule (even three  $\text{H}_2\text{O} \cdots \text{O}$  interactions) are not easily exchanged for one weaker interaction with the protein surface. Such an interaction would also involve the release of other water molecules from the TMAO and peptide surface to the bulk. Our recent molecular dynamics simulations of TMAO and dipeptide systems confirm such an explanation of the observed effects [31]. In those studies, a TMAO molecule was oriented toward the model dipeptide surface with its hydrophobic part, enhancing the hydration layer of the peptide, and avoided any direct contact, maintaining its strongly bounded water molecules. These two different mechanisms, or two different modes of competition for water in osmolyte–peptide solutions, are not directly noticeable in the shape of the osmolytes' spectra; however, the possibility of such indirect interactions are reflected in the shape of the amide I band of the K-peptide and their influence on thermal stability of K-peptide aggregates. The presumed peptide dehydration in a TMAO solution may be beneficial at first, as indicated by the position of the  $\beta$ -sheet band; however, this dehydration may promote aggregation and the general irreversibility of the denaturation processes at higher temperatures, as seen in the DSC thermograms.

**Author Contributions:** Conceptualization, J.W. and P.B.; Formal analysis, J.G., B.C. and P.B.; Funding acquisition, P.B.; Investigation, J.G. and B.C.; Methodology, P.B.; Project administration, P.B.; Software, P.B.; Supervision, P.B.; Visualization, J.G., B.C. and P.B.; Writing—Original Draft, J.G., B.C., J.W. and P.B.; Writing—Review and Editing, J.W. and P.B. All authors have read and agreed to the published version of the manuscript.

**Funding:** This research was funded by the National Science Centre, Poland (grant 2017/26/D/NZ1/00497).

**Data Availability Statement:** All of the data can be made available upon request.

**Conflicts of Interest:** The authors declare no conflict of interest.

### Abbreviations

The following abbreviations are used in this manuscript:

AA	Amino acid
ATR	Attenuated total reflectance
CPCM	Conductor-like polarizable continuum model
DFT	Density functional theory
DMSO	Dimethyl sulfoxide
DSC	Differential scanning calorimetry
FTIR	Fourier-transform infrared spectroscopy
NAGMA	<i>N</i> -acetyl-glycine-methylamide
TMAO	Trimethylamine <i>N</i> -oxide

## References

- Sunde, M.; Serpell, L.C.; Bartlam, M.; Fraser, P.E.; Pepys, M.B.; Blake, C.C. Common core structure of amyloid fibrils by synchrotron X-ray diffraction. Edited by F. E. Cohen. *J. Mol. Biol.* **1997**, *273*, 729–739. <https://doi.org/10.1006/jmbi.1997.1348>.
- Makin, O.S.; Serpell, L.C. Structures for amyloid fibrils. *FEBS J.* **2005**, *272*, 5950–5961. <https://doi.org/10.1111/j.1742-4658.2005.05025.x>.
- Hill, S.E.; Miti, T.; Richmond, T.; Muschol, M. Spatial Extent of Charge Repulsion Regulates Assembly Pathways for Lysozyme Amyloid Fibrils. *PLoS ONE* **2011**, *6*, e18171. <https://doi.org/10.1371/journal.pone.0018171>.
- Chiti, F.; Dobson, C.M. Protein Misfolding, Functional Amyloid, and Human Disease. *Annu. Rev. Biochem.* **2006**, *75*, 333–366. <https://doi.org/10.1146/annurev.biochem.75.101304.123901>.
- Glabe, C.G. Structural Classification of Toxic Amyloid Oligomers. *J. Biol. Chem.* **2008**, *283*, 29639–29643. <https://doi.org/10.1074/jbc.R800016200>.
- Kayed, R.; Head, E.; Thompson, J.L.; McIntire, T.M.; Milton, S.C.; Cotman, C.W.; Glabe, C.G. Common Structure of Soluble Amyloid Oligomers Implies Common Mechanism of Pathogenesis. *Science* **2003**, *300*, 486–489. <https://doi.org/10.1126/science.1079469>.
- Hård, T.; Lendel, C. Inhibition of Amyloid Formation. *J. Mol. Biol.* **2012**, *421*, 441–465. <https://doi.org/10.1016/j.jmb.2011.12.062>.
- Sabate, R.; Rousseau, F.; Schymkowitz, J.; Ventura, S. What Makes a Protein Sequence a Prion? *PLoS Comput. Biol.* **2015**, *11*, e1004013. <https://doi.org/10.1371/journal.pcbi.1004013>.
- Cohen, T.; Frydman-Marom, A.; Rechter, M.; Gazit, E. Inhibition of Amyloid Fibril Formation and Cytotoxicity by Hydroxyindole Derivatives. *Biochemistry* **2006**, *45*, 4727–4735. <https://doi.org/10.1021/bi051525c>.
- Tanaka, N.; Morimoto, Y.; Noguchi, Y.; Tada, T.; Waku, T.; Kunugi, S.; Morii, T.; Lee, Y.F.; Konno, T.; Takahashi, N. The Mechanism of Fibril Formation of a Non-inhibitory Serpin Ovalbumin Revealed by the Identification of Amyloidogenic Core Regions\*. *J. Biol. Chem.* **2011**, *286*, 5884–5894. <https://doi.org/10.1074/jbc.M110.176396>.
- Balbach, J.J.; Ishii, Y.; Antzutkin, O.N.; Leapman, R.D.; Rizzo, N.W.; Dyda, F.; Reed, J.; Tycko, R. Amyloid Fibril Formation by A $\beta$ 16–22, a Seven-Residue Fragment of the Alzheimer's  $\beta$ -Amyloid Peptide, and Structural Characterization by Solid State NMR. *Biochemistry* **2000**, *39*, 13748–13759. <https://doi.org/10.1021/bi0011330>.
- Mannem, R.; Yousuf, M.; Sreerama, L. Nanostructures Formed by Custom-Made Peptides Based on Amyloid Peptide Sequences and Their Inhibition by 2-Hydroxynaphthoquinone. *Front. Chem.* **2020**, *8*, 684. <https://doi.org/10.3389/fchem.2020.00684>.
- Krebs, M.R.; Wilkins, D.K.; Chung, E.W.; Pitkeathly, M.C.; Chamberlain, A.K.; Zurdo, J.; Robinson, C.V.; Dobson, C.M. Formation and seeding of amyloid fibrils from wild-type hen lysozyme and a peptide fragment from the  $\beta$ -domain. Edited by P. E. Wright. *J. Mol. Biol.* **2000**, *300*, 541–549. <https://doi.org/10.1006/jmbi.2000.3862>.
- Frare, E.; Polverino de Laureto, P.; Zurdo, J.; Dobson, C.M.; Fontana, A. A Highly Amyloidogenic Region of Hen Lysozyme. *J. Mol. Biol.* **2004**, *340*, 1153–1165. <https://doi.org/10.1016/j.jmb.2004.05.056>.
- Sugimoto, Y.; Kamada, Y.; Tokunaga, Y.; Shinohara, H.; Matsumoto, M.; Kusakabe, T.; Ohkuri, T.; Ueda, T. Aggregates with lysozyme and ovalbumin show features of amyloid-like fibrils. *Biochem. Cell Biol.* **2011**, *89*, 533–544. <https://doi.org/10.1139/o11-041>.
- Tokunaga, Y.; Sakakibara, Y.; Kamada, Y.; Watanabe, K.i.; Sugimoto, Y. Analysis of Core Region from Egg White Lysozyme Forming Amyloid Fibrils. *Int. J. Biol. Sci.* **2013**, *9*, 219–227. <https://doi.org/10.7150/ijbs.5380>.
- Arnaudov, L.N.; de Vries, R. Thermally Induced Fibrillar Aggregation of Hen Egg White Lysozyme. *Biophys. J.* **2005**, *88*, 515–526. <https://doi.org/10.1529/biophysj.104.048819>.
- Antosova, A.; Chelli, B.; Bystrenova, E.; Siposova, K.; Valle, F.; Imrich, J.; Vilkova, M.; Kristian, P.; Biscarini, F.; Gazova, Z. Structure-activity relationship of acridine derivatives to amyloid aggregation of lysozyme. *Biochim. Et Biophys. Acta (BBA)-Gen. Subj.* **2011**, *1810*, 465–474. <https://doi.org/10.1016/j.bbagen.2011.01.007>.
- Ramshini, H.; Mannini, B.; Khodayari, K.; Ebrahim-Habibi, A.; Moghaddasi, A.S.; Tayebee, R.; Chiti, F. Bis(indolyl)phenylmethane derivatives are effective small molecules for inhibition of amyloid fibril formation by hen lysozyme. *Eur. J. Med. Chem.* **2016**, *124*, 361–371. <https://doi.org/10.1016/j.ejmech.2016.08.056>.
- Wawer, J.; Kaczkowska, E.; Karczewski, J.; Olszewski, M.; Augustin-Nowacka, D.; Krakowiak, J. Amyloid fibril formation in the presence of water structure-affecting solutes. *Biophys. Chem.* **2019**, *254*, 106265. <https://doi.org/10.1016/j.bpc.2019.106265>.
- Wawer, J.; Szociński, M.; Olszewski, M.; Piątek, R.; Naczka, M.; Krakowiak, J. Influence of the ionic strength on the amyloid fibrillogenesis of hen egg white lysozyme. *Int. J. Biol. Macromol.* **2019**, *121*, 63–70. <https://doi.org/10.1016/j.ijbiomac.2018.09.165>.
- Humblet-Hua, N.P.; Sagis, L.M.C.; van der Linden, E. Effects of Flow on Hen Egg White Lysozyme (HEWL) Fibril Formation: Length Distribution, Flexibility, and Kinetics. *J. Agric. Food Chem.* **2008**, *56*, 11875–11882. <https://doi.org/10.1021/jf803377n>.
- Nedaei, H.; Saboury, A.A.; Meratan, A.A.; Karami, L.; Sawyer, L.; Kaboudin, B.; Jooyan, N.; Ghasemi, A. Polyphenolic self-association accounts for redirecting a high-yielding amyloid aggregation. *J. Mol. Liq.* **2018**, *266*, 291–298. <https://doi.org/10.1016/j.molliq.2018.06.044>.
- Ramshini, H.; Mohammad-Zadeh, M.; Ebrahim-Habibi, A. Inhibition of amyloid fibril formation and cytotoxicity by a chemical analog of Curcumin as a stable inhibitor. *Int. J. Biol. Macromol.* **2015**, *78*, 396–404. <https://doi.org/10.1016/j.ijbiomac.2015.04.038>.
- Gazova, Z.; Bellova, A.; Daxnerova, Z.; Imrich, J.; Kristian, P.; Tomascikova, J.; Bagelova, J.; Fedunova, D.; Antalík, M. Acridine derivatives inhibit lysozyme aggregation. *Eur. Biophys. J.* **2008**, *37*, 1261–1270. <https://doi.org/10.1007/s00249-008-0313-0>.
- Bruzdziak, P.; Panuszko, A.; Stangret, J. Influence of Osmolytes on Protein and Water Structure: A Step To Understanding the Mechanism of Protein Stabilization. *J. Phys. Chem. B* **2013**, *117*, 11502–11508. <https://doi.org/10.1021/jp404780c>.

27. Wawer, J.; Krakowiak, J.; Szociński, M.; Lustig, Z.; Olszewski, M.; Szostak, K. Inhibition of amyloid fibril formation of hen egg white lysozyme by trimethylamine N-oxide at low pH. *Int. J. Biol. Macromol.* **2014**, *70*, 214–221. <https://doi.org/10.1016/j.ijbiomac.2014.06.057>.
28. Oprzeska-Zingrebe, E.A.; Smiatek, J. Aqueous Mixtures of Urea and Trimethylamine-N-oxide: Evidence for Kosmotropic or Chaotropic Behavior? *J. Phys. Chem. B* **2019**, *123*, 4415–4424. <https://doi.org/10.1021/acs.jpbc.9b02598>.
29. Oprzeska-Zingrebe, E.A.; Smiatek, J. Interactions of a DNA G-quadruplex with TMAO and urea: A molecular dynamics study on co-solute compensation mechanisms. *Phys. Chem. Chem. Phys.* **2021**, *23*, 1254–1264. <https://doi.org/10.1039/D0CP05356B>.
30. Panuszko, A.; Bruździak, P.; Śmiechowski, M.; Stasiulewicz, M.; Stefaniak, J.; Stangret, J. DMSO hydration redefined: Unraveling the hydrophobic hydration of solutes with a mixed hydrophilic–hydrophobic characteristic. *J. Mol. Liq.* **2019**, *294*, 111661. <https://doi.org/10.1016/j.molliq.2019.111661>.
31. Panuszko, A.; Pieloszczyk, M.; Kuffel, A.; Jacek, K.; Biernacki, K.A.; Demkowicz, S.; Stangret, J.; Bruździak, P. Hydration of Simple Model Peptides in Aqueous Osmolyte Solutions. *Int. J. Mol. Sci.* **2021**, *22*, 9350. <https://doi.org/10.3390/ijms22179350>.
32. Bruździak, P. Vapor correction of FTIR spectra—A simple automatic least squares approach. *Spectrochim. Acta Part A Mol. Biomol. Spectrosc.* **2019**, *223*, 117373. <https://doi.org/10.1016/j.saa.2019.117373>.
33. Bruździak, P.; Panuszko, A.; Kaczkowska, E.; Piotrowski, B.; Dagher, A.; Demkowicz, S.; Stangret, J. Taurine as a water structure breaker and protein stabilizer. *Amino Acids* **2018**, *50*, 125–140. <https://doi.org/10.1007/s00726-017-2499-x>.
34. Panuszko, A.; Bruździak, P.; Kaczkowska, E.; Stangret, J. General Mechanism of Osmolytes' Influence on Protein Stability Irrespective of the Type of Osmolyte Cosolvent. *J. Phys. Chem. B* **2016**, *120*, 11159–11169. <https://doi.org/10.1021/acs.jpbc.6b10119>.
35. Frisch, M.J.; Trucks, G.W.; Schlegel, H.B.; Scuseria, G.E.; Robb, M.A.; Cheeseman, J.R.; Scalmani, G.; Barone, V.; Mennucci, B.; Petersson, G.A.; et al. *Gaussian 09, Revision D.01*; Gaussian Inc.: Wallingford, CT, USA, 2009. <https://doi.org/10.1159/000348293>.
36. Lee, C.; Yang, W.; Parr, R.G. Development of the Colle-Salvetti correlation-energy formula into a functional of the electron density. *Phys. Rev. B* **1988**, *37*, 785–789. <https://doi.org/10.1103/physrevb.37.785>.
37. Becke, A.D. Density-functional thermochemistry. III. The role of exact exchange. *J. Chem. Phys.* **1993**, *98*, 5648–5652. <https://doi.org/10.1063/1.464913>.
38. Ditchfield, R.; Hehre, W.J.; Pople, J.A. Self-Consistent Molecular-Orbital Methods. IX. An Extended Gaussian-Type Basis for Molecular-Orbital Studies of Organic Molecules. *J. Chem. Phys.* **1971**, *54*, 724–728. <https://doi.org/10.1063/1.1674902>.
39. Cossi, M.; Rega, N.; Scalmani, G.; Barone, V. Energies, structures, and electronic properties of molecules in solution with the C-PCM solvation model. *J. Comput. Chem.* **2003**, *24*, 669–681. <https://doi.org/10.1002/jcc.10189>.
40. Barone, V.; Cossi, M. Quantum calculation of molecular energies and energy gradients in solution by a conductor solvent model. *J. Phys. Chem. A* **1998**, *102*, 1995–2001. <https://doi.org/10.1021/jp9716997>.
41. Grimme, S.; Ehrlich, S.; Goerigk, L. Effect of the damping function in dispersion corrected density functional theory. *J. Comput. Chem.* **2011**, *32*, 1456–1465. <https://doi.org/10.1002/jcc.21759>.
42. Hanwell, M.D.; Curtis, D.E.; Lonie, D.C.; Vandermeersch, T.; Zurek, E.; Hutchison, G.R. Avogadro: An advanced semantic chemical editor, visualization, and analysis platform. *J. Cheminformatics* **2012**, *4*, 17. <https://doi.org/10.1186/1758-2946-4-17>.
43. Biernacki, K.A.; Kaczkowska, E.; Bruździak, P. Aqueous solutions of NMA, Na<sub>2</sub>HPO<sub>4</sub>, and NaH<sub>2</sub>PO<sub>4</sub> as models for interaction studies in phosphate–protein systems. *J. Mol. Liq.* **2018**, *265*, 361–371. <https://doi.org/10.1016/j.molliq.2018.05.104>.
44. Bruździak, P.; Panuszko, A.; Piotrowski, B.; Stangret, J. Structural changes of a simple peptide—Trpzip-1—In aqueous solutions and the corresponding hydration phenomena under the influence of temperature. *J. Mol. Liq.* **2019**, *277*, 532–540. <https://doi.org/10.1016/j.molliq.2018.12.101>.
45. Panuszko, A.; Nowak, M.; Bruździak, P.; Stasiulewicz, M.; Stangret, J. Amides as models to study the hydration of proteins and peptides—Spectroscopic and theoretical approach on hydration in various temperatures. *J. Mol. Liq.* **2019**, *278*, 706–715. <https://doi.org/10.1016/j.molliq.2019.01.086>.