

Article

The Application of Granulated Expanded Glass Aggregate with Cement Grout as an Alternative Solution for Sub-Grade and Frost-Protection Sub-Base Layer in Road Construction

Marzena Kurpińska , Beata Grzyl, Marek Pszczola  and Adam Kristowski 

Gdansk University of Technology, Faculty of Civil and Environmental Engineering, 80-233 Gdansk, Poland; beata.grzyl@pg.edu.pl (B.G.); marek.pszczola@pg.edu.pl (M.P.); adam.kristowski@pg.edu.pl (A.K.)

* Correspondence: marzena.kurpanska@pg.edu.pl

Received: 27 September 2019; Accepted: 25 October 2019; Published: 28 October 2019



Abstract: The purpose of the research was to assess the possibility of using granulated expanded glass aggregate (GEGA) with cement grout as a replacement of a sub-grade and frost-protection layer, made of natural fine aggregates (NATU), stabilized with a hydraulic binder. Instead of traditional parts of the road construction, such as the sub-grade and frost-protection layer with the application of fine aggregate, stabilized with cement, the authors propose only one layer, made of lightweight water-permeable material, containing GEGA with a grain size from 8 to 11.2 mm. In the article the authors present the physical properties of the materials, applied for the road layers, the properties of the fine aggregate, stabilized with cement, and those of the cement composite with GEGA as an alternative solution. The laboratory test results of fine aggregates, stabilized with cement and of cement composites with GEGA, are presented. Porosity, volume density, compressive strength, and frost resistance are being researched. The results of those tests are meant to play an essential role in designing the thickness of road layers. Different types of pavement structure (asphalt and concrete) and different values of road load are being considered in the given work. The paper is concluded with considerations on an innovative solution, involving the use of ecological materials.

Keywords: road design; building construction; sub-grade layer; permeable frost protection layer; lightweight aggregate; granulated ash aggregate; artificial neural networks

1. Introduction

The road construction sector all around the world is the largest consumer of natural aggregates [1]. It is reported that global annual use of the aggregates constitutes over 40 billion tons, 90% of which is produced on the basis of natural resources. The rest are aggregates, made of the recycled materials (about 5%), synthetic aggregates (2%) and aggregates, extracted from the sea area (about 2%) [2]. Despite the presence of a number of areas, rich in natural aggregate sources, certain countries are characterized by a deficit of natural aggregates. It is often the case that a fine aggregate is inapplicable in construction because of too small a grain size.

The use of industrial by-products in road construction can contribute to the discussion on reducing the consumption of natural resources and reducing the areas of landfills. Glass waste could be considered as a potential alternative secondary raw material in road construction [3–6]. Waste glass is an excellent material to be subjected to repeated recycling [7,8]. At the same time, due to its composition and structure, glass does not pose any hazard to the environment as a recycled material. It is estimated that annually, in Europe, 11–40 kg of glass waste is generated per capita, depending on the country.

Overall production of waste is constantly growing. Glass constitutes approximately 10%–15% of municipal waste, depending on the waste management practices in the country.

According to the World Bank, annual waste production is about 2 billion tons [9–12]. The development of waste glass processing technology allows reaching up to 100% recycling, which contributes to the reduction of energy consumption for processing primary raw materials for the production of glass, i.e., sand, soda, and limestone dust [13,14]. There are many concerns about the industrial use of the recycled products. With this in mind, many studies are being carried out, confirming the possibility of using waste materials, including glass cullet [15]. Expanded glass aggregate, where cullet is the key component, is proposed to be applied for the improvement of the road sub-grade. The possibility of using shredded waste glass in road engineering, as a substitute for coarse aggregate, was carried out by [16–19]. Another solution was the use of shredded glass instead of natural sand. Such studies were conducted by [20–23]. Another lightweight aggregate, which has already been used in road construction, is produced from expanded clay or fly ash, coming from coal combustion or municipal waste incineration plants. It has been well-known and successfully used for quite a long time [24–29]. The examples of application of lightweight aggregate fillers, presented in the publications, confirm that this solution is technically feasible in the road construction industry, and its significant advantages influence the possibility of reducing costs of road construction as compared to traditional materials [30–39]. Therefore, the authors have made an attempt to use GEGA as a substitute for the natural aggregate in the sub-grade and the frost protection layer of the road foundation. The main assumption, which is made here, is that construction material should meet all the requirements, related to, among others, mechanical properties, durability, and economic coefficient [40,41].

The authors put forward the thesis that it is possible to use GEGA of diameter 8/11.2 mm with cement grout, instead of two layers: a sub-grade and a frost-protection layer of the road. At the same time, special attention has been paid to the quality and the cost of the recycled materials. The main assumption was that the quality, cost, and durability of the new solution cannot turn out less beneficial for the interested parties than the solution, traditionally used in road construction. The main profit of the new solution implementation can be seen in lower consumption of natural resources, application of waste glass and, therefore, a reduction of CO₂ emission.

On the basis of the research, carried out by [42,43], the authors assessed the suitability of the glass waste in the form of foam glass as an alternative to natural sand, used as a sub-grade and a frost-protection layer of the pavement road.

The authors of the article below undertook a research into the possibilities of using GEGA from the waste glass in road construction. The main goal of the research was to find a new solution that would allow reducing the consumption of natural resources and, instead, to use the material derived from glass waste recycling.

2. Materials and Methods

2.1. Assumptions of Pavement Structure and Adopted Materials

Two main types of pavement structure were analyzed: type 1—flexible pavement with asphalt mixture layers and base course, made of an unbound mixture, and type 2—rigid pavement with a concrete slab in a wearing course layer and base course layer, made of a mixture, bound with a hydraulic binder. Traffic categories were marked in accordance with the guidelines for the road pavement design in Poland [44]. For flexible pavements, road structures for heavy traffic (22.00–52.00 million equivalent standard axle load (ESAL) of 100 kN/lane), for medium traffic (2.50–7.30 million of ESAL of 100 kN/lane) and for light traffic (0.09–0.50 million of ESAL of 100 kN/lane) were assumed. Additionally, there were subsurface and groundwater conditions for cohesive soils adopted, e.g., sandy clay, and high groundwater level. In the analyzed examples, the proposed new solution, which was assumed, was frost protection layer performing the function of a drainage layer at

the same time. For rigid pavements, road structures for heavy traffic (42.63–101.25 million of ESAL of 100 kN/lane), for medium traffic (6.39–15.99 million of ESAL of 100 kN/lane), and for light traffic (0.15–0.75 million of ESAL of 100 kN/lane) were assumed. Additionally, subsurface and groundwater conditions, as well as conditions for the application of a drainage layer, were assumed analogously as for flexible pavements. The layout of type 1 and 2 pavement layers is schematically shown in Figure 1.

Traffic Load—Heavy Traffic			
FLEXIBLE PAVEMENT with asphalt mixture layers TRADITIONAL SOLUTION	FLEXIBLE PAVEMENT with asphalt mixture layers GEGA SOLUTION	RIGID PAVEMENT with concrete slab TRADITIONAL SOLUTION	RIGID PAVEMENT with concrete slab GEGA SOLUTION
Wearing course, made of asphalt mixture	Wearing course, made of asphalt mixture	Wearing course, made of cement concrete	Wearing course, made of cement concrete
Binder course layer	Binder course layer	Slip layer	Slip layer
Base course layer II	Base course layer II	Base course layer	Base course layer
Base course layer I	Base course layer I	Sub-base layer	Sub-base layer
Sub-base layer	Sub-base layer	Frost resistant layer	permeable concrete, made of GEGA
Frost protection layer	permeable concrete, made of GEGA	Improved sub-grade	
Improved sub-grade		Subgrade, native soil—excavation	
Subgrade, native soil—excavation			

(a)

Traffic Load—Medium Traffic			
FLEXIBLE pavement TRADITIONAL SOLUTION	FLEXIBLE pavement GEGA SOLUTION	RIGID pavement TRADITIONAL SOLUTION	RIGID pavement GEGA SOLUTION
Wearing course, made of asphalt mixture	Wearing course, made of asphalt mixture	Wearing course, made of cement concrete	Wearing course, made of cement concrete
Binder course layer	Binder course layer	Slip layer	Slip layer
Base course layer II	Base course layer II	Base course layer	Base course layer
Base course layer I	Base course layer I	Sub-base layer	Sub-base layer
Sub-base layer	Sub-base layer	Frost protection layer	permeable concrete, made of GEGA
Frost protection layer	permeable concrete, made of GEGA	Improved sub-grade	
Improved sub-grade		Subgrade, native soil—excavation	
Subgrade, native soil—excavation			

(b)

Figure 1. Cont.

Traffic Load—Light Traffic			
FLEXIBLE pavement TRADITIONAL SOLUTION	FLEXIBLE pavement GEGA SOLUTION	RIGID pavement TRADITIONAL SOLUTION	RIGID pavement GEGA SOLUTION
Wearing course, made of asphalt mixture	Wearing course, made of asphalt mixture	Wearing course layer, made of cement concrete	Wearing course layer, made of cement concrete
Binder course layer	Binder course layer	Base course layer	Base course layer
Base course layer	Base course layer	Frost protection layer	permeable concrete, made of GEGA
Frost protection layer	permeable concrete, made of GEGA	Improved sub-grade	
Improved sub-grade		Subgrade, native soil—excavation	
Subgrade, native soil—excavation			

(c)

Figure 1. Structure of road layers design for flexible and rigid pavements—traditional and with the use of permeable concrete, made of GEGA for traffic load: (a) heavy traffic, (b) medium traffic, and (c) light traffic.

The new solution assumes the substitution of the traditional solution with one, single layer, made of permeable lightweight GEGA concrete, constituting, at the same time, a frost protection course and improved soil sub-grade. The characteristic feature of the permeable lightweight GEGA concrete is liquid permeability. Porous lightweight GEGA concrete is freeze and thaw resistant. Permeable concretes can be made of a single- or double- fraction aggregate with a grain size of more than 4 mm. The amount of cement paste shall be used in the quantity, allowing to cover individual grains of the aggregate and to create an interfacial transition zone (ITZ) between the grains of the aggregate.

Figure 1 shows structural layers of flexible and rigid pavements, made of traditional and permeable concrete, and the ones, made of permeable concrete with solutions using GEGA for traffic load: heavy, medium, and light traffic.

Apparent, the density of condensed fine aggregate, stabilized with cement, ranges up to 1700–2000 kg/m³ whereas, in the case of using artificial aggregates with the addition of fly ash or clay, the apparent density reaches only 1400 kg/m³. If we use GEGA, the apparent density does not exceed 1000 kg/m³. The size of the spaces between the grains can be controlled to some extent by the grain size of the coarse aggregate. The amount and the size of the spaces between the grains depends on the diameter of the aggregate and on the amount of cement grout surrounding the grains of the aggregate and partially filling the pores. The greater the void content of the aggregate composition is, and the less pore filling is, the larger the porosity and the higher the water permeability are. Additionally, the amount of slurry or mortar will influence the quality of ITZ between the grains of the aggregate and cement grout. With the increase of the amount of slurry and mortar, mechanical properties of the composite will be more beneficial. The overall porosity of the composite and, therefore, permeability change with the thickness of the ITZ. The higher the amount of slurry is, the thicker the contact zone is and, at the same time, the higher compression strength is.


2.2. Materials

Portland cement CEM II/A-V 42.5 N with 20% fly ash, according to EN 197-1, was used to perform the tests. Chemical content and physical properties of the cement CEM II/A-V 42.5 N are shown in Table 1. The tests have been carried out in the laboratory of Gdańsk University of Technology.

Table 1. Chemical content and physical properties of the cement CEM II/A-V 42.5 N.

Setting Start Time (min)	Setting End Time (min)	Compressive Strength (MPa)			Blaine Fineness (cm ² /g)	Coal Content (%)	Water Demand (%)
		2 days	28 days				
195	265	21.3	51.7		3521	3.0	28.5
Content (%)							
SiO ₂	Al ₂ O ₃	Fe ₂ O ₃	CaO	MgO	SO ₃	Na ₂ eq	Cl
25.0	8.8	3.2	54.0	1.2	2.6	0.86	0.042

The main component of cement is CaO, and its content is 54%, while the content of SiO₂ silica is approximately 25%. Natural fine aggregate with a grain size from 0 to 4 mm (NATU), meeting the requirements of EN 12620: 2010, was used for the test. Distribution curves of NATU are shown in Figure 2. The chemical composition of NATU is shown in Tables 2 and 3. Figure 3 presents microscopic images of fine aggregate grains in the vicinity of cement paste.


**Figure 2.** Distribution curves of aggregates size.**Table 2.** Chemical composition of the aggregate.

Aggregate Type	Content (%)									
	SiO ₂	Al ₂ O ₃	Fe ₂ O ₃	CaO	MgO	SO ₃	Na ₂ O	K ₂ O	TiO ₂	Coal Content
NATU	97.5	0.8	0.08	0.3	-	0.05	-	-	0.1	-
GEGA	63.3	0.74	-	14.19	2.98	0.32	13.35	0.57	-	4.53

Table 3. Physical properties of the aggregates.

Property		NATU	GEGA
Water absorption WA_{24}	(%)	1.8	17.8
Particle density ρ_a	(kg/m^3)	2640	350
Oven dried particle density ρ_{rd}	(kg/m^3)	2520	310
Saturated surface-dry particle density ρ_{ssd}	(kg/m^3)	2560	330
Porosity P	(%)	n.s.	42
Crumble indicator X_r	(%)	n.s.	25.9
pH after 24 h	-	n.s.	11.9
Loose bulk density ρ_b	(kg/m^3)	1550	180
Compact bulk density ρ_c	(kg/m^3)	1760	255
Thermal conductivity of 40 cm layer of the aggregate	W/m·K	n.s.	0.69

n.s.—not studied.

**Figure 3.** Aggregate NATU (a) grains to 4 mm; (b) grain surface, 100 \times ; (c) grain structure after cutting the sample (grain in the vicinity of cement paste), 1000 \times .

Artificial aggregate (GEGA) is manufactured from clear construction glass recycling and municipal waste recycling. The resources for clear glass production are quartz sand and additives, such as: sodium and calcium carbonate, flux: boron and lead oxide. Glass waste is ground in a ball mill and, next, cement is added, as well as fly ash, zeolite, metakaolin, foaming substances, and water. Then, out of the mix the granules are formed and placed in the furnace at 900 °C. Finally, a light-gray or beige porous granulated product is obtained. Granulated aggregate is sorted according to grain diameter. For this research GEGA (Figure 4) with a grain size ranging from 8 to 11.2 mm was applied. Its chemical and physical properties are shown in Tables 2 and 3.




Figure 4. Granulated expanded glass aggregate GEGA (a); grains at 11.2 mm; (b) structure of GEGA, 200 \times ; (c) structure of GEGA, 1000 \times .

The main component of NATU and GEGA is SiO₂ silica, and its content in NATU is 97.5% and in GEGA is 63.3%.

2.3. Preparation of Mix and Samples

Research of the properties was carried out for two variants of the material, marked NATU and GEGA. In the first variant, NATU, the samples were representative for the material, used in the cement-stabilized sub-grade and for a frost protection road layer in Poland. A mixture of NATU, stabilized with cement, contained 20% fly ash. Properties of the components are presented in Tables 1–3. NATU mixture, bound with a hydraulic binder, was prepared with CEM II/A-V 42.5 N cement, 129 kg; NATU, 1742 kg; and water, 107 kg. The composition was designed on the basis of the tests, aiming to determine the maximum density and optimal moisture content of the material. The components of the mixture were mixed in a mechanical mixer. First, NATU was dry-mixed with cement for 2 min, then water was added and mixed for another 3 min. The maximum density of NATU with cement and water of $\max = 1.84 \text{ g/cm}^3$ was determined and the optimum water content constituted up to 7.97%. The relationship of bulk density and moisture is shown in Figure 5.




Figure 5. Relationship of the bulk density of NATU ρ_d with moisture w .

The mixture was poured into special cylindrical forms. Samples were prepared in special cylindrical forms of dimensions of $\varnothing 100 \text{ mm}$; $h = 115 \text{ mm}$ (Figure 6a,b). The samples were compacted in three layers, 25 strokes per layer, by means of the Proctor method according to standard EN 13286-2, using a $\varnothing 50 \text{ mm}$ compactor of a weight of 2.5 kg, falling freely from a height of 305 mm. In total, 18 cylindrical samples of the dimensions of $\varnothing 100 \text{ mm}$ and $h = 115 \text{ mm}$ were made, for compressive strength testing at 7, 28, and 56 days. There were six samples tested on each date



of the test. Additionally, six cubic samples of dimensions of $10 \times 10 \times 10 \text{ cm}^3$ were made for frost resistance testing.



Figure 6. Preparation of the samples made of fine aggregate with cement: cylindrical form (a); samples (b).

Samples, having been prepared, were stored for 24 h in a mold, at a temperature of $20 \pm 2 \text{ }^\circ\text{C}$, followed by subsequent storage in a chamber, in the humidity of 95%–100% and temperature of $20 \pm 2 \text{ }^\circ\text{C}$ and protected against drying. Three days before the test, the samples were submerged in water of the temperature of $20 \pm 2 \text{ }^\circ\text{C}$. One hour before compressive strength testing, the samples were taken out of the water and their surface was dried. Volume density, compressive strength, and frost resistance coefficient were tested.

The material with GEGA was proposed as a new solution. The mixture of the following composition was designed: CEM II/A-V 42.5 N, 205 kg; NATU, 90 kg; GEGA, 150 kg; water, 125 kg. The components of the mixture were mixed in a mechanical mixer. First, the slurry, composed of cement and water, was mixed for 2 min. Then, NATU was added and the mortar was mixed for next 1 min. GEGA was added to the mortar and mixed for 2 min.

The mixture was laid to special cylindrical molds of $\text{Ø} 100 \text{ mm}$; $h = 115 \text{ mm}$. The mix was compacted 25 times in two layers. The compaction method in accordance with the EN 206 standard is suggested by the authors. During concrete compacting, a hand-rammer of $\text{Ø} 50 \text{ mm}$ and weight of 1 kg was used. In order to ensure proper merger of the components, it is important to properly compact permeable ready mix with GEGA. It should be noted that too much compaction energy will reduce the porosity of the concrete, which, in turn, will reduce its permeability. Additionally, compacting shall be carried out in a way that prevents damage of the grains of the lightweight GEGA aggregate. For the compressive strength testing at 7, 28, and 56 days, 18 cylindrical samples of $\text{Ø} 100 \text{ mm}$ and $h = 115 \text{ mm}$ were made as shown in Figure 7a,b. There were six samples, tested on each assigned date of the tests. Additionally, 6 cubic samples of dimensions of $10 \times 10 \times 10 \text{ cm}^3$ were made for frost resistance testing. Test samples were stored for 24 h in molds at a temperature of $20 \pm 2 \text{ }^\circ\text{C}$, followed by subsequent storage in a chamber at a humidity of 95%–100% and temperature of $20 \pm 2 \text{ }^\circ\text{C}$ and protected against drying. One hour before the resistance test, the samples were taken out of the chamber and left to dry in the air at a temperature of $20 \pm 2 \text{ }^\circ\text{C}$. Volume density, compressive strength, and frost resistance coefficient were tested.




Figure 7. Preparation of a sample mixture with GEGA (a). Sample of the mixture with GEGA for compression strength tests (b).

2.4. Test Methods

2.4.1. Volume Density Test and Porosity Test

Volume density was determined for three samples, made of NATU and for three samples of the material, made of GEGA:

$$\rho_0 = \frac{m_0}{V}, \quad (1)$$

where ρ_0 is the volume density of the materials, m_0 is the weight of the cylindrical sample, and V is the volume of cylindrical sample.

Volume density tests were carried out on cylindrical samples, intended for compressive strength testing. The volume of the sample was determined by measuring the sample's dimensions.

Material porosity was marked as f_V and defined as a ratio of the pores volume in the cylindrical sample to the total volume V of the sample. Porosity is the ratio of the volume of pass-through pores in a unit of the volume of a sample:

$$f_V = \frac{V_p}{V}, \quad 0 < f_V \leq 1 \quad (2)$$

Due to the relationship:

$$V = V_p + V_s \quad (3)$$

Volume porosity is defined as:

$$f_V = \frac{(V - V_s)}{V} = 1 - \frac{V_s}{V} \quad (4)$$

where f_V is the material porosity, V is the total volume, V_p is the volume of pores, and V_s is the volume of the solid material.

A porosity test was carried out on three cylindrical samples. The sample volume was determined by the measurement of its dimensions. The volume of open pores was determined by measuring water volume which permeated inside the sample. Water, filling in the pores, was measured by capillary forces, without any external pressure. The pore volume V_p was obtained by determining the mass of water that penetrated the pores of the sample. It has been assumed that 1 dm³ of water is equal to 1 kg.

2.4.2. Compressive Strength Tests

The compressive strength test was carried out in the Advantest 9, Controls, Liscate MI, Italy) in a uniaxial state of stress in accordance with the procedure, defined in EN 13286-41. For the compressive strength testing at 7, 28, and 56 days, 18 cylindrical samples of \varnothing 100 mm and $h = 115$ were made. On each assigned date six cylindrical samples were tested. Compressive strength of the material was

determined on the basis of the arithmetic mean of the results for all six. It was assumed that none of the results can deviate from the mean more than 10%. Standard deviation was determined.

2.4.3. Frost Resistance Coefficient Tests

Samples for frost resistance coefficient test were stored for 28 days in a chamber with the humidity of 95%–100%, and temperature of 20 ± 2 °C. Then, they were submerged in water for 24 h, and placed in a frost chamber. Then they underwent 14 frost and thaw cycles. One cycle procedure involves freezing the samples for 8 h in the temperature of -23 ± 2 °C and thawing them for 16 h in the temperature of 18 ± 2 °C. Frost resistance coefficient was determined for three samples in accordance with Equation (5). The average compression strength R_c^{Z-O} was adopted for the calculations. The following frost resistance coefficient was adopted:

$$M = \frac{R_c^{Z-O}}{R_c} \quad (5)$$

for $M_{min} = 0.7$; where R_c^{Z-O} is the average compressive strength of the samples, subjected to freeze-thaw cycles, and R_c is the average compressive strength of reference samples (cured in air and water).

3. Results and Discussion

3.1. Volume Density Tests

The volume density of NATU and GEGA were determined at seven and 28 days, by measuring and weighing cylindrical samples according to Equation (1). The result is the arithmetic mean of the values, determined for six NATU and six GEGA cylindrical samples. The results are presented in Figure 8.




Figure 8. Change in apparent density.

3.2. Compressive Strength Tests

The average compressive strength of NATU, tested on six samples, was 1.3 MPa (standard deviation $s = 0.2$ MPa), while the average compressive strength of the six samples (cylinders) on the 28th day was 3.2 MPa ($s = 0.4$ MPa). At 56 days, the average compressive strength was 3.8 MPa ($s = 0.3$ MPa). It is shown in Figure 9a. Compressive strength test of the material with GEGA was performed at seven days on six cylindrical samples and it was 1.9 MPa ($s = 0.2$ MPa), while on the 28th day the average compressive strength of the six cylindrical samples was 3.7 MPa ($s = 0.3$ MPa). At 56 days, the average compressive strength was 4.9 ($s = 0.7$ MPa). Test results are presented in Figure 9b.




Figure 9. Growth of compression strength with time: (a) NATU, (b) GEGA.

The carried out frost resistance tests of NATU and GEGA have shown that both materials have met Polish Technical Requirements WT-5 2010, “Mixtures bound with a hydraulic binder for national roads” and that the frost resistance index, calculated according to Equation (5), was higher than the required minimum $M_{\min} = 0.7$, where the NATU frost resistance index was 0.74 and the GEGA frost resistance index was 0.94.

4. Analysis and Application of the Traditional Pavement Structure and with Use of a GEGA Permeable Layer

Taking into account favorable properties of permeable concrete, the analysis of the possibilities to apply this material for a road course in typical solutions for pavement structure was carried out in accordance with Polish requirements [45,46].

The procedure for the calculation of the required thickness of the lightweight GEGA permeable concrete course, as an alternative to a typical frost protection course and improved soil sub-grade, was carried out in accordance with the guidelines, contained in [47–49]. For each of the analyzed solutions the values of elastic deflections “w” on the surface of the improved sub-grade course and on the surface of the sub-base courses of the pavement structure were determined. Calculations were

carried out using BISAR 3.0 software (Bitumen Stress Analysis in Roads, Shell, Gdansk, Poland). The required $E_{equivalent}$ substitute modulus on the surface of the analyzed layers was calculated by means of using the Boussinesq equation (Equation (6)) from the theory of elastic half-space, which is the following:

$$E_{equivalent} = \frac{q \times D \times (1 - \nu^2)}{w}, \quad (6)$$

where $E_{equivalent}$ is the substitute modulus, determined on the surface of sub-base course layer of pavement structure and on the surface of improved subgrade, MPa; q is the contact pressure of the wheel $q = 0.65$ kPa; D is the substitute diameter of the wheel tract, $D = 0.313$ m; ν is Poisson's ratio, $\nu = 0.3$; and w is the deflection on the surface of road profile, m.

Tables 4–6 summarize the proposal of application of lightweight concrete sub-grade course containing GEGA material instead of traditional frost-resistant layer and improved sub-grade course. Calculations of the required thickness of the GEGA concrete road pavement layer for flexible and rigid pavements were carried out, depending on the traffic category, i.e., the traffic load. The results of the calculations, presented in Tables 4–6, refer to three selected representative road traffic categories, according to [44], representing heavy, medium, and light traffic.

Table 4. Resulting structural layers of flexible and rigid pavements—traditional and permeable concrete—made of GEGA, solutions for heavy traffic.

Type of Pavement							
Traffic Load—Heavy Traffic							
22.00–52.00 mln of ESAL 100 kN/lane in the design period of 30 years				42.63–101.25 mln of ESAL 100 kN/lane in the design period of 30 years			
FLEXIBLE PAVEMENT with asphalt mixture layers and base course, made of unbound mixture TRADITIONAL SOLUTION		FLEXIBLE PAVEMENT with asphalt mixture layers and base course, made of unbound mixture GEGA SOLUTION		RIGID PAVEMENT with concrete slab in wearing layer and base course, made of mixture, bound with hydraulic binder TRADITIONAL SOLUTION		RIGID PAVEMENT with concrete slab in wearing layer and base course, made of mixture, bound with hydraulic binder GEGA SOLUTION	
4 cm	Wearing course, made of asphalt mixture	4 cm	Wearing course, made of asphalt mixture	27 cm	Wearing course, made of cement concrete—dowelled and anchored	27 cm	Wearing course, made of cement concrete—dowelled and anchored
8 cm	Binder course layer, made of asphalt concrete	8 cm	Binder course layer, made of asphalt concrete	-	Slip layer: surface dressing or geotextile fabrics	-	Slip layer: surface dressing or geotextile fabrics
16 cm	Base course layer, made of asphalt concrete	16 cm	Base course layer, made of asphalt concrete	18 cm	Base course layer, made of mixture bound with 8/10 hydraulic binder	18 cm	Base course layer, made of mixture bound with 8/10 hydraulic binder
20 cm	Base course layer, made of unbound mixture with C 90/3 aggregate	20 cm	Base course layer, made of unbound mixture with C 90/3 aggregate	15 cm	Sub-base layer, made of mixture, bound with C5/6 hydraulic binder	15 cm	Sub-base layer, made of mixture, bound with C5/6 hydraulic binder
15 cm	Sub-base layer, made of mixture, bound with hydraulic binder	15 cm	Sub-base layer, made of mixture, bound with hydraulic binder	20 cm	Frost resistant layer, made of unbound mixture with a function of drainage layer	28 cm	Permeable concrete, made of GEGA
20 cm	Frost resistant layer made of unbound mixture, with a function of drainage layer	28 cm	Permeable concrete, made of GEGA	25 cm	Improved sub-grade, made of soil, stabilized with hydraulic binder		
25 cm	Improved sub-grade, made of soil stabilized with hydraulic binder			Subgrade, native soil—excavation			
Subgrade, native soil—excavation							



Table 5. Resulted structural layers of flexible and rigid pavements—traditional and permeable concrete, made of GEGA, solutions for medium traffic.

Type of Pavement							
Traffic Load—Medium Traffic							
2.50–7.30 mln of ESAL 100 kN/lane in the design period of 30 years				6.39–15.99 mln of ESAL 100 kN/lane in the design period of 30 years			
FLEXIBLE PAVEMENT TRADITIONAL SOLUTION		FLEXIBLE PAVEMENT GEGA SOLUTION		RIGID PAVEMENT TRADITIONAL SOLUTION		RIGID PAVEMENT GEGA SOLUTION	
4 cm	Wearing course, made of asphalt mixture	4 cm	Wearing course, made of asphalt mixture	23 cm	Wearing course, made of cement concrete—dowelled and anchored	23 cm	Wearing course, made of cement concrete—dowelled and anchored
6 cm	Binder course layer, made of asphalt concrete	6 cm	Binder course layer, made of asphalt concrete	-	Slip layer: surface dressing or geotextile fabrics	-	Slip layer: surface dressing or geotextile fabrics
10 cm	Base course layer, made of asphalt concrete	10 cm	Base course layer, made of asphalt concrete	20 cm	Base course layer, made of mixture, bound with C 5/6 hydraulic binder	20 cm	Base course layer, made of mixture, bound with C 5/6 hydraulic binder
20 cm	Base course layer, made of unbound mixture with C 90/3 aggregate	20 cm	Base course layer, made of unbound mixture with C 90/3 aggregate	15 cm	Sub-base layer, made of mixture, bound with C 3/4 hydraulic binder	15 cm	Sub-base layer, made of mixture, bound with C 3/4 hydraulic binder
15 cm	Sub-base layer, made of mixture, bound with hydraulic binder	15 cm	Sub-base layer, made of mixture, bound with hydraulic binder	20 cm	Frost protection layer, made of unbound mixture; with a function of drainage layer	23 cm	Permeable concrete, made of GEGA
20 cm	Frost protection layer, made of unbound mixture, with a function of drainage layer	23 cm	Permeable concrete, made of GEGA	25 cm	Improved sub-grade made of soil, stabilized with hydraulic binder		
25 cm	Improved sub-grade, made of soil, stabilized with hydraulic binder					Subgrade, native soil—excavation	
	Subgrade, native soil—excavation						



Table 6. Resulted structural layers of flexible and rigid pavements—traditional and permeable concrete, made of GEGA, solutions for light traffic.

Type of Pavement							
Traffic Load—Light Traffic							
0.09–0.50 mln of ESAL 100 kN/lane in the design period of 30 years				0.15–0.75 mln of ESAL 100 kN/lane in the design period of 30 years			
FLEXIBLE PAVEMENT TRADITIONAL SOLUTION		FLEXIBLE PAVEMENT GEGA SOLUTION		RIGID PAVEMENT TRADITIONAL SOLUTION		RIGID PAVEMENT GEGA SOLUTION	
4 cm	Wearing course, made of asphalt mixture	4 cm	Wearing course, made of asphalt mixture	24 cm	Wearing course layer, made of cement concrete—undowelled	24 cm	Wearing course layer, made of cement concrete—undowelled
8 cm	Binder course layer, made of asphalt concrete	8 cm	Binder course layer, made of asphalt concrete	30 cm	Base course layer, made of unbound mixture, made of C 50/30 aggregate	30 cm	Base course layer, made of unbound mixture, made of C 50/30 aggregate
20 cm	Base course layer, made of unbound mixture with C 90/3 aggregate	20 cm	Base course layer, made of unbound mixture with C 90/3 aggregate	22 cm	Frost protection layer made of unbound mixture; with a function of drainage layer	18 cm	Permeable concrete, made of GEGA
22 cm	Frost protection layer, made of unbound mixture; with a function of drainage layer	18 cm	Permeable concrete, made of GEGA	24 cm	Improved sub-grade, made of soil, stabilized with hydraulic binder		
24 cm	Improved sub-grade, made of soil, stabilized with hydraulic binder			Subgrade, native soil—excavation			
Subgrade, native soil—excavation							



The computational analysis showed that it is possible to replace the traditional solution of the frost protection course and the improved soil sub-grade course with a single course of lightweight concrete containing GEGA material. The proposed alternative solution which may be used in both flexible and rigid pavement structures, features the required load-bearing capacity and durability parameters.

5. Conclusions

The completed tests and analyses allow the following conclusions to be drawn:

1. The research confirmed that the road sub-grade of permeable concrete, made of GEGA, has similar mechanical properties to a sub-grade with NATU and can function as a frost protection layer for the road sub-base. Additionally, the material with GEGA is permeable to liquids. Therefore, it is possible to obtain a lightweight material with GEGA of the mechanical properties, meeting the requirements, imposed on the frost protection layer, made of natural aggregate NATU, stabilized with a hydraulic binder. Thus, it is possible to substitute the sub-grade and the frost-protection sub-base with a single layer, made of lightweight material with GEGA.
2. The analysis has shown that practical implementation of the proposed solution is technically justified in the case of flexible and rigid pavements. Application of the recycled material with GEGA allows an effective construction of the road pavement, maintaining the required load-bearing capacity and durability parameters.
3. The proposed solution, concerning the use of recycled materials is fully coherent with the idea of environment protection and sustainable development of the economy, not only in Europe, but worldwide. The application of GEGA allows limiting the mining of the NATU materials, due to which environmental degradation can be reduced.
4. It is recommended to carry out further research on the LCC (life cycle costs) analysis, conducted for flexible and rigid pavements, for selected traffic categories and for two technologies of road pavement construction [50–52].
5. Further research into lightweight aggregate's compressive strength increase shall be carried out and the elastic modulus shall be determined, as well as volume flow rate, depending on the porosity.
6. Rapid development in industrial application of GEGA and other lightweight aggregates, manufactured from recycled materials, requires a proposal and implementation of the design methods for the materials with synthetic aggregates and recycled aggregates.

Author Contributions: Conceptualization: M.K.; methodology: M.K. and M.P.; validation: A.K. and B.G.; formal analysis: M.K.; investigation: M.K., M.P., and B.G.; resources: M.K. and A.K.; data curation: A.K.; writing—original draft preparation: M.K., A.K., and M.P.; writing—review and editing: M.K., B.G., and A.K.; supervision: M.K.; project administration: M.K. and A.K.; funding acquisition: M.K.

Funding: This research received no external funding.

Conflicts of Interest: The authors declare no conflict of interest.

References

1. Karim, Y.; Khan, Z.; Alsofi, M.S.; Yunus, M. A Review on Recycled, Aggregates for the Construction Industry. *Am. J. Civ. Eng. Archit.* **2016**, *4*, 27–33. [CrossRef]
2. A Sustainable Aggregates Industry for a Sustainable Europe. Available online: <http://www.uepg.eu/> (accessed on 7 May 2019).
3. Sikora, P.; Augustyniak, A.; Cendrowski, K.; Horszczaruk, E.; Rucinska, T.; Nawrotek, P.; Mijowska, E. Characterization of mechanical and bactericidal properties of cement mortars containing waste glass aggregate and nanomaterials. *Materials* **2016**, *9*, 701. [CrossRef] [PubMed]
4. Najduchowska, M.; Rozycka, K.; Rolka, G. Ocena możliwości wykorzystania stłuczki szklanej w przemyśle budowlanym w aspekcie jej wpływu na środowisko naturalne. *Prace ICI MB* **2014**, *17*, 1–10. (In Polish)

5. Sikora, P.; Horszczaruk, E.; Skoczylas, K.; Rucinska, T. Thermal properties of cement mortars containing waste glass aggregate and nanosilica. *Procedia Eng.* **2017**, *196*, 159–166. [[CrossRef](#)]
6. Du, H.; Tan, K.H. Concrete with recycled glass as fine aggregates. *ACI Mater. J.* **2014**, *111*, 47–58.
7. Chung, S.-Y.; Elrahman, M.; Sikora, P.; Rucinska, T.; Horszczaruk, E.; Stephan, D. Evaluation of the Effects of Crushed and Expanded Waste Glass Aggregate on the Material Properties of Lightweight Concrete Using Image-Based Approaches. *Materials* **2017**, *10*, 1354. [[CrossRef](#)] [[PubMed](#)]
8. Lo, T.Y.; Tang, W.C.; Cui, H.Z. The effects of aggregate properties on lightweight concrete. *Build. Environ.* **2007**, *42*, 3025–3029. [[CrossRef](#)]
9. Waste Statistics. Available online: https://ec.europa.eu/eurostat/statistics-explained/index.php/Waste_statistics (accessed on 7 May 2019).
10. Kurpińska, M.; Ferenc, T. Application of lightweight cement composite with foamed glass aggregate in shell structures. *Shell Struct. Theory Appl.* **2018**, *4*, 549–552.
11. Jamshidi, A.; Kurumisawa, K.; Nawa, T.; Igarashi, T. Performance of pavements incorporating waste glass: The current state of the art. *Renew. Sustain. Energy* **2016**, *64*, 211–236. [[CrossRef](#)]
12. Ganjian, E.; Jalull, G.; Sadeghi-Pouya, H. Using waste materials and by-products to produce concrete paving blocks. *Constr. Build. Mater.* **2015**, *77*, 270–275. [[CrossRef](#)]
13. Arnold, G.; Werkmeister, S.; Alabaster, D. The effect of adding recycled glass on the performance of base course aggregate. *N. Z. Transp. Agency Res. Rep.* **2008**, *351*, 40.
14. Ulsen, C.; Kahn, H.; Hawlitschek, G.; Masini, E.A.; Angulo, S.C.; John, V.M. Production of recycled sand from construction and demolition waste. *Constr. Build. Mater.* **2013**, *40*, 1168–1173. [[CrossRef](#)]
15. Shi, C.; Zheng, K. A review on the use of waste glasses in the production of cement and concrete. *Resour. Conserv. Recycl.* **2007**, *52*, 234–247. [[CrossRef](#)]
16. Domagala, L. Structural lightweight aggregate concrete. In *Civil Engineering*; Cracow University of Technology: Cracow, Poland, 2014. (In Polish)
17. Šeputytė-Jucikė, J.; Sinica, M. The effect of expanded glass and polystyrene waste on the properties of lightweight aggregate concrete. *Eng. Struct. Technol.* **2016**, *8*, 31–40. [[CrossRef](#)]
18. Gonawala, R.J.; Khapre, S.; Kumar, R.; Chauhan, K.A. Suitability of EAF slag and GGBFS mix as cementitious base/sub-base layer for low volume road construction. *Int. J. Geotech. Eng.* **2019**. [[CrossRef](#)]
19. Biswal, D.R.; Sahoo, U.C.; Dash, S.R. Mechanical characteristics of cement stabilised granular lateritic soils for use as structural layer of pavement. *Road Mater. Pavement Des.* **2018**. [[CrossRef](#)]
20. Canakci, H.; Güllü, M.I.; Dwle, K. Effect of Glass Powder Added Grout for Deep Mixing of Marginal Sand with clay. *Arab. J. Sci. Eng.* **2018**, *43*, 1583–1595. [[CrossRef](#)]
21. Del Rey, I.; Ayuso, J.; Barbudo, A.; Galvín, A.P.; Agrela, F.; de Brito, J. Feasibility study of cement-treated 0–8 mm recycled aggregates from construction and demolition waste as road base layer. *Road Mater. Pavement Des.* **2015**, *17*, 678–692. [[CrossRef](#)]
22. Poutos, K.H.; Alani, A.M.; Walden, P.J.; Sangha, C.M. Relative temperature changes within concrete made with glass aggregates. *Constr. Build. Mater.* **2006**, *22*, 557–565. [[CrossRef](#)]
23. Park, S.B.; Lee, B.C.; Kim, J.H. Studies on mechanical properties of concrete containing waste glass aggregates. *Cement Concrete Res.* **2004**, *34*, 2181–2189. [[CrossRef](#)]
24. Wang, H.; Huang, W. Durability of self-consolidating concrete using waste LCD glass. *Constr. Build. Mater.* **2010**, *24*, 1008–1013. [[CrossRef](#)]
25. Liu, S.; Wang, S.; Tang, W.; Hu, N.; Wei, J. Inhibitory Effect of Waste Glass Powder on ASR expansion induced by waste glass aggregate materials. *Materials* **2015**, *8*, 6849–6862. [[CrossRef](#)] [[PubMed](#)]
26. Rashad, A.M. Recycled waste glass as fine aggregate replacement in cementitious materials based on Portland cement. *Const. Build. Mater.* **2014**, *72*, 340–357. [[CrossRef](#)]
27. Xi, Y.; Li, Y.; Xie, Z.; Lee, J.S. Utilization of solid wastes (waste glass or rubber particles) as aggregate in concrete. In *Proceedings of the International Workshop on Sustainable Development and Concrete Technology*, Beijing, China, 20–21 May 2004.
28. Shayan, A.; Xu, A. Performance of glass powder as a pozzolanic materials in concrete: A field trial on concrete slabs. *Cement Concrete Res.* **2006**, *36*, 457–468. [[CrossRef](#)]
29. Gallaway, B.M. *A Manual on the Use of Lightweight Aggregate in Flexible Pavement Systems*; Shale Clay Slate Institute: Washington, DC, USA, 1969.



30. Arulrajah, A.; Disfani, M.; Horpibulsuk, S. Sustainable Usage of Construction and Demolition Materials in Roads and Footpaths. *Sustain. Issues Civ. Eng.* **2017**. [[CrossRef](#)]
31. Airey, G.D.; Collo, A.C.; Thom, N.H.; Zoorob, S.E.; Shiratori, A. Laboratory evaluation of secondary aggregates in bituminous mixtures. *J. Assoc. Asphalt Paving Technol.* **2004**, *73*, 731–769.
32. Limbachiya, M.C. Bulk engineering and durability properties of washed glass sand concrete. *Constr. Build. Mater.* **2008**, *23*, 1078–1083. [[CrossRef](#)]
33. Segui, P.; Dore, G.; Bilodeau, J.-P.; Morasse, S. Innovative materials for road insulation in cold climates: Foam glass aggregate. In Proceedings of the 2016 Conference and Exhibition of the Transportation Association of Canada—Efficient Transportation—Managing the Demand, Toronto, ON, Canada, 22–28 September 2016.
34. Omidimoaf, E.; Rajabi, A.M.; Abdelgader, H.S.; Kurpińska, M.; Wilde, K. Effect of coarse grain aggregate on strength parameters of two-stage concrete. *Mater. Bud.* **2019**, *3*, 1–3. [[CrossRef](#)]
35. Mariak, A.; Kurpińska, M.; Wilde, K. Maturity curve for estimating the in-place strength of high performance concrete. *MATEC Web Conf.* **2019**, *262*, 06007. [[CrossRef](#)]
36. Mariak, A.; Kurpińska, M. The effect of macro polymer fibres length and content on the fibre reinforced concrete. *MATEC Web Conf.* **2018**, *219*, 03004. [[CrossRef](#)]
37. Kurpińska, M.; Małasiewicz, A. *Der Betonschutz vor der Wirkung der Aggressiven Umgebung*; Tagungsbericht/Ibausil, 15. Internationale Baustofftagung; Bauhaus-Universität Weimar/F.A. Finger-Institut für Baustoffkunde: Weimar, Germany, 2003.
38. Kurpińska, M. Properties of concrete impregnated using epoxy composition. *Roads Bridges* **2011**, *10*, 59–80.
39. Al-Sibahy, A.; Edwards, R. Mechanical and thermal properties of novel lightweight concrete mixtures containing recycled glass and metakaolin. *Constr. Build. Mater.* **2012**, *31*, 157–167. [[CrossRef](#)]
40. Grzyl, B.; Apollo, M.; Miszewska-Urbańska, E.; Kristowski, A. The criteria for evaluation and selection the best tender applied by the authorities in Poland and selected EU countries. *MATEC Web Conf.* **2018**, *219*, 04006. [[CrossRef](#)]
41. Grzyl, B.; Miszewska-Urbańska, E.; Apollo, M. The life cycle cost of a building from the point of view of environmental criteria of selecting the most beneficial offer in the area of competitive tendering. *Web Conf.* **2017**, *17*, 00028. [[CrossRef](#)]
42. Frydenlund, T.E.; Aaboe, R. Granulated Expanded Glass Aggregate—A new vision in road construction. In Proceedings of the XXII PIARC World Road Congress, Durban, South Africa, 19–25 October 2003.
43. Kurpińska, M.; Ferenc, T. Effect of porosity on physical properties of lightweight cement composite with foamed glass aggregate. *ITM Web Conf.* **2017**, *15*, 6005. [[CrossRef](#)]
44. Pszczoła, M.; Judycki, J.; Ryś, D. Evaluation of pavement temperatures in Poland during winter conditions. *Transp. Res. Procedia* **2016**, *14*, 738–747. [[CrossRef](#)]
45. GDDKiA. *Catalogue of Typical Flexible and Rigid Road Pavement Structures, Order No. 31 of the General Director for National Roads and Motorways of 16.06.2014*; Generalna Dyrekcja Dróg Krajowych i Autostrad: Warszawa, Poland, 2014.
46. GDDKiA. *Catalogue of Typical Flexible and Rigid Road Pavement Structures, Order No. 30 of the General Director for National Roads and Motorways of 16.06.2014*; Generalna Dyrekcja Dróg Krajowych i Autostrad: Warszawa, Poland, 2014.
47. Cheng, A.; Hsu, H.-M.; Chao, S.-J.; Lin, K.-L. Experimental Study on Properties of Pervious Concrete Made with Recycled Aggregate. *Int. J. Pavement Res. Technol.* **2011**, *4*, 104–110.
48. Judycki, J.; Jaskuła, P.; Pszczoła, M.; Ryś, D.; Jaczewski, M.; Alenowicz, J.; Dołycki, B.; Stienss, M. *Analyses and Designing of Flexible and Semi-Rigid Road Pavement Structures*; Wydawnictwa Komunikacji i Łączności: Warsaw, Poland, 2014.
49. Judycki, J.; Jaskuła, P.; Pszczoła, M.; Ryś, D.; Jaczewski, M.; Alenowicz, J.; Stienss, M. New Polish Catalogue of Typical Flexible and Semi-Rigid Pavements. *MATEC Web Conf.* **2017**, *122*, 4002. [[CrossRef](#)]
50. Kristowski, A.; Grzyl, B.; Kurpińska, M.; Pszczoła, M. The rigid and flexible road pavements in terms of life cycle costs. In Proceedings of the Creative Construction Conference, Ljubljana, Slovenia, 30 June–3 July 2018. [[CrossRef](#)]

51. Grzyl, B.; Siemaszko, A. The Life Cycle Assessment and Life Cycle Cost in public works contracts. *Web Conf.* **2018**, *44*, 00047. [[CrossRef](#)]
52. Grzyl, B.; Kristowski, A.; Jamroz, K.; Gobis, A. Methods of estimating the cost of traffic safety equipment's life cycle. *MATEC Web Conf.* **2017**, *122*, 02003. [[CrossRef](#)]



© 2019 by the authors. Licensee MDPI, Basel, Switzerland. This article is an open access article distributed under the terms and conditions of the Creative Commons Attribution (CC BY) license (<http://creativecommons.org/licenses/by/4.0/>).